

My PhilGEPS

My Organization

My Profile

Opportunities

Catalogue

Directory

About PhilGEPS

Pending Task | Notices | Award Notices

Wednesday, June 21, 2023 07:37 AM

Venus Solano MNWD

» Log-out

Bid Notice Abstract

[Detail Tracking Report](#)

Request for Quotation (RFQ)

Reference Number 9867032

Procuring Entity METROPOLITAN NAGA WATER DISTRICT

Title Supply, Delivery, Installation and Commissioning of Brand New VFD at San Agustin Reservoir (PR 23-06-0249)

Area of Delivery Camarines Sur

 [Printable Version](#)

Solicitation Number:	PR 23-06-0249	Status	Active
Trade Agreement:	Implementing Rules and Regulations	Associated Components	1
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)		
Classification:	Goods	Bid Supplements	0
Category:	Industrial Machinery and Equipment		
Approved Budget for the Contract:	PHP 332,500.00	Document Request List	0
Delivery Period:	30 Day/s		
Client Agency:			
Contact Person:	Venus C. Solano Procurement Analyst A 40 J.Miranda Ave., Naga City Camarines Sur Philippines 4400 63-54-4737813 Ext.117 63-54-4739288 mnwdbac@yahoo.com	Date Published	21/06/2023
		Last Updated / Time	21/06/2023 12:00 AM
		Closing Date / Time	26/06/2023 5:00 PM

Description

ITEM NO. ITEM & DESCRIPTION QTY UNIT

1 Supply, Delivery, Installation and Commissioning of Brand New Variable Frequency Drive, 40 HP, 460V, 3 Phase, 60hz 1 LOT

Technical Specification:

- Unit must be brand new and shall conforms with global safety standards CE, UL, EN/IEC.
- The enclosure shall be IP21 or higher, powder coated based finished using epoxy powder paint oven baked.
- Unit must be equipped with 1 unit rotary type manual transfer switch rated in amperes for switching to back-up panel.
- The Enclosure must be equipped with four (4) four cooling fans: (2) two for intake and (2) two for exhaust.
- All wirings, conduits and other electrical materials needed for the installation of unit to and from tapping point shall be borne by the supplier
- Pressure transmitter shall be 0-10 bars, 4-20ma and 1/20 NPT rating shall include installation of plumbing materials to and from tapping point by the supplier.
- The unit must be equipped with a removable keypad tactical response LCD display with built in real-time clock capable of functions showing remote toggle and graphical monitoring.
- The unit must be equipped with a 3phase surge protective device
- The unit must be equipped with an analog/digital voltmeter, ammeter and hourmeter reading located outside the panel.

TERMS AND CONDITIONS:

- Provide after sales service and availability of materials
- Attached product brochure with technical specifications
- Provide hardcopy and soft copy of VFD Manuals with circuit diagram upon commissioning
- Conduct free training and transfer of technology on handling and troubleshooting of equipment by MNWD Personnel upon commissioning
- The unit must be SCADA adaptable.
- The unit must be capable to operate with the existing 3 Phase power supply provided by the local utility company and standby generator set upon commissioning.
- Supplier must conduct free site inspection were equipment to be installed and must adapt with the existing grounding system of the facility.

Note:

- VAT Inclusive
- FOB MNWD, Naga City
- Partial Delivery shall not be accepted
- Supplier must submit brochure

Documentary Requirements to submit:

- Mayor's/Business Permit
- PhilGEPS Registration Number / Certificate of Platinum Membership
- Income/Business Tax Returns (for ABCs above Php 500k)
- Omnibus Sworn Statement

**Incomplete or non-submission of the required Documentary Requirements shall be automatically disqualified